App. F. IX-4

Previous References.

1955:56.
(GB)

File No. 17-55

Serial Nos. 3, 4, 11, 15, 16 19

Later References.

GENERAL AND REVENUE SECRETARIAT

Serial Nos. 6

8 30 E

Part B for June 1956

SUBJECT

Revised estimate for forming a layout of Sites behind All India Radio, Yadavagiri Extension before

LH165-67 2.6.56.

The Chairman, M.T.B.
C.S.H.
C.R.

Vasantha
17/7/56

Serial No.

Letter No D2 C 514/54-55 & 27-1-55 from the Chairman, C.I.T.B, Mysore, regarding revised estimate for Rs 39,000 for forming up a layout of sites behind All India Radio, Jayanagar extension

submitting with a memo forwarding the revised estimate for Rs 39,000 to the C.E. for scrutiny and early return

No. 8/L.9/2

2) [illegible]

E.O No 276 27/5.2.55

Sri [illegible] 27/1/55

Dy. Ch. Engr. 15.2.55

Dy. Ch. Engr. 19.2.55

D/2 784 21.2.55

Ex. Engr. 21/2/55

Subdn. 22/2/55

Dy. Ch. Engr. 25/2/55

(164)

RB. 10781 17.2.55

[illegible]
Asst. secretary,
Education & Leg. Affairs

U.O.No. 13028 /RB-54-55 dated, 21.3.55. 22

Encl - 8.

Retransmitted.

4) The estimate does not admit of any technical scrutiny for want of the particulars detailed below.

(a) Except for a layout plan, no detailed drawings are furnished in respect of the slabbed drains, box drains, road tunnels, pipe crossings, cisterns, retaining walls, construction of steps on the Northern side of the layout & etc., The quantities provided for in the estimate do not admit of any verification in the absence of detailed drawings.

(b) The layout plan furnished does not indicate the proposed water supply and sewage lines. Three dotted lines are shown

24 M

26/3

NOTE.—Contn. sheet

Revised estimate for forming a layout behind All India Radio – Mysore.

7 9 1 1

File No. of 195 | Mysore Government Secretariat

Serial No.

are shown running right across the layout. In case they are power lines, it is imperative to avoid formation of sites below or very near the power lines. From the layout plan furnished, it is seen that the Power lines cross the sites numbered 4, 7, 41 and 46 and run very close to the sites numbered 8 and 29.

(c) The estimate amounting to Rs. 3,275/- in respect of water supply, stated to have been received from the water supply Division, has not been furnished.

(d) Information as to when the work was started and completed and if the approved schedule rates of the year during which the several items of work were completed, are provided for in respect of the non-tendered items, is not furnished.

It is stated that the total area of the sites formed now (as per the revised estimate) is 11,463 syds. as against the area of 3,947 s.yds. originally proposed to be formed. These details as well as the roads actually formed are not indicated in the layout plan.

Secretary to Government,
Edn. & L.S.G. Departments,
Bangalore.

R. Madhavan
(R. MADHAVAN) 19/3
Deputy Chief Engineer.
19.3.55

IS/19-3-55.

→ A draft letter is submitted to get further particulars
Mia 1/4.4.55

9 Issued
11/4

To, the chairman, DTB
L 87 dt 20-4-55
calls for certain particulars

WD 07074—GPB—80,000—5-10-54

Sd/ A Mrs

Revised estimate for forming a layout road All India Radio Mysore 3

Mysore Government Secretariat | 7967 ME File No. 2395 of 195 | [App. F. III 2

Serial No.

Letter No D2. C. 514/52-55 dated 28. 6. 55 from the Chairman, City STB Mysore forwarding the estimate called for along with the connected records.

Submitted 1) The file may be sent to the Chief Engineer for transmittal memo is prepared for kind approval

R6/7 U.O.No. 83/RB)-7-55

2) Forwarded to the Chief Engineer for Scrutiny of the estimate and early return.

RB 32-87 12-7-55 (649)

for Secy Edn & LSG Depts

R6/7 Mg 7/7

10. file is issued to Supdg C.E. Br III

3) U.O.No. 5587 /RB-55-56 dated, 27-9-55 29.9.55

Encl. One U.O. File

4) Retransmitted.

5) The estimate is scrutinised for Rs.39,000/- subject to the observations detailed in the accompanying note.

RB 265 167-11- 20/7/55

Please flag 'C'

R. Jayaraman 29/9

The Secretary to Government, Education & L.S.G. Departments, Bangalore.

(R. MADHAVAN) Deputy Chief Engineer 26.9.55

IS/24-9-55.

6) Dft letter to the chairman STB. requesting him to furnish his remarks to the observations of the CE is prepared for favour of kind approval (Remarks of the C.E flag C - forthcoming marked 'A' & 'B' are omitted to be included in the draft)

R 2/11/55 Mg 2/11

7) Issue

Issued to the chairman STB for a report L 9905, STB 7-55-15 dt 11.11.55

NOTE.—Contn. sheet

R 21/11

Revised estimate for forming & laying of 4 lts
bituminous Bellary Road Yeddiyapura Bangalore

Mysore Government Secretariat

File No. 2895 / 6294 First Stage of 195

Serial No. (773) RB 9180 17-12-55

Letter No. 82.C.576/54-55 dated 23-11-55 from the Chairman MTB forwarding replies to the observations of the CE.

Submitted (14) the file may be sent to CE for further remarks. Proposal means is put for his approval.

U.O.No. 238 / dt 13-12-55

(15) Forwarded to the Chief Engineer for further remarks and early return of the file.

Sd/- Illegible
for Secretary to Government
Public Works Department

Sd/- M.S. 5/12

Sd/- 15/12

Sd/- Illegible 16/12

Sd/- Illegible 27/12/55.

U.O.No. 10623 ~~RB~~-55-56 dated, 25-1-56

Retransmitted.

(16) The certificate of scrutiny furnished in this office No.U.C.5587/RB-55-56 dated 29-9-1955, is confirmed. The replies furnished by the Chairman, Trust Board, may be accepted. The points observed in respect of water supply are to be borne in mind while executing the work.

27 JAN Recd

Sd/- M. Narayana Iyengar
(H. ANANTHACHAR)
Chief Engineer of Mysore.
(Draft appd by CE)
23.1.56

Secretary to Government,
Education & L.S.G.
Departments,
Bangalore.

IS/23-1-56.

WD 07074—GPP—80,000—5-10-54

Revised estimate for forming a layout of site bearing No. Basia Roads Yelahanka [App. F. III 2 Encl 5

Mysore Government Secretariat

File No. 6294 ML of 195

Serial No.

Submitted:-(17) The estimate has been sanctioned by the CE for Rs 39,000/- (vide para 10). The revised estimate for Rs 39,000/- may perhaps be sanctioned with the observation of the Chief Engineer made at para (16).

For orders

R 31/1

(18) The original estimate for Rs 10,000 was sanctioned by the T.B as revised to Rs 39,000 in which provision is also reported to have been made for extra work, for forming more site area and for providing underground drainage and water supply facilities. According to the revised scheme, the total area of sites to be formed is 11,463 sq yds and an average rate of Rs 3-7-0 is expected to be realised. The total amount of realisation at this rate works out to Rs 40,404/-. The revised estimate for Rs 39,000/- may therefore be sanctioned

Vide chairman's letter of 27-1-55 (page 1)

M. C. 2/2

(19) There is the estimate for Rs 21,000/- for putting up underground drainage

Is the cost of providing water mains in the streets included in the estimates

PTO

Note.—Contn. Sheet

Revised estimate for forming a layout of site behind All India Radio, Yadavagiri Extension (Item 8 2nd)

File No. 6294 M of 195

Mysore Government Secretariat

Serial No.

Submitted 20/ The file relating to the estimate for Rs 21,000/- for the formation of Additional site behind All India Radio (2nd stage) has been sent to the C.E. on 20-1-56 vide D.No 7458 M

for orders whether the remarks of the Site sent to CE may be accepted

Ref Para (19)

29/2

21/ The separate estimate for Rs 21,000 for the II stage of the layout has been submitted separately. It is pending with the C.E.

This revised ~~estimate~~ estimate for Rs 39,000 contains provision of Rs 3480/- for water supply work and of Rs 7000 for underground drainage. Ref Para 19.

please see flg "F" (Items 11 & 12)

M.S. 1/3

22)

The Revised estimate for Rs 39,000/- may be sanctioned. (The points observed by the Chief Engineer in respect of water supply are suggested in Para 16, will be communicated. The suggestions in respect of water supply works are noted in Page 10 of the file)

OFFICE OF THE MINISTER FOR PUBLIC HEALTH & LOCAL-SELF GOVERNMENT
24 MAR
No. 612

19024

Secy (Com & Dep)

23) may be ord 11/3

19694 mor.

17.3.56

24)

Hon'ble Minister (L.S.G.)

25)

27.4.56

21 MAR 1956
U.O. No. 540

WD 0260-3 GPB—PMZ—S—1,30,000—21-5-55.

Mysore Government
Secretariat

Revised estimate for forming a lay out of new vehicle Bridge road

[App. F. 111-2

6294/1327 File No: Yelahanka of 195 Estates on Public Works

Serial No.

Submitted with a dft G.O. for issue approval — Asst Engr (25)

Please put up a revised draft
M. 4/5

L 4/5

Submitted with the revised dft for issue approval

L 5/5

M. 16/5

Issue —

23/5

Letter No. B.C. 514/565 dated 12-5-56 from the chairman/M.T.B.

According to the Revised estimate for Rs 39,000/- as sanctioned by the Chief Engineer with certain observations

Issued to the chairman M.T.B

Copies sent to

1. C.E. Mysore Division

L 4165-67/ 7063 17-5-56 5 2 6/a

B
Ref 16
M.T.B

Note.—Contn. Sheet

(1)

G. O. C. 514 /54-55.

Encl. 1) Abstract Estimate.
2) Detailed Estimate with necessary Plates
3) office note.
4) T.R 12 Copy.
5) Comparative Statement
6) Accepted Tendered Rate List.
7) plan
8) original Estimate

OFFICE OF THE CHAIRMAN,
CITY IMPROVEMENT TRUST BOARD,
POST BOX NO. 55, MYSORE.

Dated 27th January 1955

FROM
SRI S. LINGANNA,
Chairman, City Improvement Trust Board,
MYSORE.

7947

To

Sri B.M.Krishnan, B.A., I.A.S.,
Secretary to the Government of Mysore.
Education and Local Self-Government & Planning Departments,
BANGALORE.

EDUCATION
31 JAN 1955
GOVERNMENT OF MYSORE.

ITB 17 33 3

Subject :Revised estimate for forming a layout of sites behind All India Radio, Yadavagiri Extension. Mysore. (First stage).

I write to state that an estimate for Rs. 10,000/- was sanctioned by the Board in resolution No. 280 dated 28-10-1953 for forming a layout of sites behind All India Radio and most of the layout works have been carried out, after calling for quotations and obtaining approval of the Board, as the estimate was within the powers of sanction of the Board. This estimaate was originally intended for forming 16 sites only and to construct model houses thereon, as the location commanded a valuable and central position in the City. The schme for constructing 16 model houses has been sanctioned in G.O. No. L. 13130-31/ITB. 18-53-38 dated 9-1-1954 and the houses have all been completed and their disposal is being attended to by the Board. During the course of execution of the layout works, it was found that with certain extra works, some more area could be reclaimed and more sites formed. Accordingly a revised estimate has been got up for Rs. 39,000/- providing for the additional works involved in the formation of the layout.

There was no provision for underground drainage in the sactioned estimate for Rs. 10,000/- and hence a sum of Rs. 7000/- has now been provided therefor in the revised estimate. Towards water supply, an estimate for Rs. 3275/- has been received from the Executive Engineer, Water Supply Division, and this amount is included in the revised estimate.

The total area of sites to be formed will be 11,463 sq. yards

P.T.O.

against the original proposal of forming 16 sites with an area of 3947 sq. yeards. The average cost per syd. will be Rs. 3-7-0 with these revised provisions in the revised estimate. Necessary provision has also been made for semi-grouting the roads to prevent erosion and periodical repairs. The scheme will be a self-supporting one as the sites can be disposed off at the cost price or even at a higher rate.

The marginally ** noted references are herewith enclosed for kind information of Government, with a request that the revised estimate for Rs. 39,000/- may kindly be sanctioned at an early date, so as to enable this office to push through the works.

**
1. Detailed estimate,
2. Abstract estimate,
3. Comparitive statement,
4. Office note,
5. Trust Board resolution No.334, dated 29-12-1954,
6. Blue print of the layout.

Yours faithfully,

S.Linganna 27/1/55

(S.Linganna)
Chairman.

dvn)

(2)

City Improvement Trust Board Mysore.

OFFICE NOTE.

SUBJECT: Revised estimate for forming a layout of sites (first stage) behind All India Radio, in Yadavagiri Extension.

An estimate for Rs.10,000/- has been sanctioned in Trust Board resolution No.280 dated 28-10-53 for the above work under "Extension funds" and most of the layout works have been carried out, after calli for quotations and obtaining approval of the Board. This estimate was originally intended for formation of 16 sites only and to construct model houses, as the location was very important and there was deman for such built houses. While the layout works were under formation, the scheme for construction of 16 model houses was also sanctioned and the houses have now been completed and they are notified for sale. During execution of the layout works, it was found that with certain extra works, some more area could be reclaimed and more sites could be formed. Accordingly, a revised estimate has been got up providing for the additional works involved in the formation o the layout.

In the sanctioned estimate, no provision was made for underground drainage and hence a sum of Rs.7000/- has been provided for water supply and necessary underground drainage facilities. This estimate has been approved by the Board in resolution No.293 dated 24-11-1954 and this provision i now included in the revised estimate of the layo

P.T.O.

(W)

Similarly for water supply, a detailed estimate for Rs.3275/- has been received from the Water Supply Department and this provision is also included in the revised estimate. The total cost of the revised estimate is Rs.39,000/- as against the original estimate for Rs.10,000/- The total area of sites to be formed is 11,463 sq.yards as against the original proposal of forming 16 sites with an area of 3947 syds In the enclosed layout plan, the area to which the first set estimate pertains has been clearly shown and the average cost per syd. of site will be Rs.3-7-0 with these revised provisions.

As it has been considered advantageous to semi-grout the newly formed roads to prevent erosion and periodical repairs, necessary provision for semi-grouting is made in the layout works, based on the present working data of the City Municipality, Mysore.

The revised estimate may kindly be approved to obtain sanction of Government in the matter.

Sd/K.V.Rajarathnam,
Trust Board Engineer, Mysore.

Orders of the Chairman:

"Trust Board meeting".

"Copy"

Chairman. 31

DVS)

(52)

City Improvement Trust Board, Mysore.

Dated 3-1-1955.

Extract from the Proceedings of the Ordinary Meeting of the Board of Trustees for the Improvement of the City of Mysore, held on 29-12-1954

xxxx xxxx xxxx

334: Revised estimate for forming layout of sites (first stage) behind All India Radio in Yadavagiri Extension.

Office note approved. Revised estimate is sanctioned and recommended to Government.

Sd/S.Linganna,
Chairman.
29-12-54.

xxxx xxxx xxxx

"Copy"

DVS)

S. Linganna.
CHAIRMAN

69

Re:- Revised estimate for
forming a layout of sites
1890/WB between All India Radio
20-4-55 Yadavagiri, (First stage)

To, ITB. 14 55-4
The Chairman, C.P.W.B,
Nagpur

Sir,

With reference to your letter
No. D2.C.574/54-55 of 27-1-55
on the above subject, I am directed
to state as follows ~~that the C.E. who was~~
~~consulted in the matter had framed~~ made
~~his estimate for the work referred,~~—

T.S.
Please bring here
the ~~Para 4, (a) to (e)~~
~~note sheet of~~
~~the file~~

In the light of the above remarks
~~of the Deputy C.E.~~, the records are
returned herewith for retransmission
with all the particulars required to
facilitate scrutiny of the estimate.

Y.T.
Asstt.
V.D.

870/97/B 17-55-4

Mysore Government
xxxxxxxxxxxxxxxx
20-4-55

Education & s,
Bangalore.

The Chairman,
City Improvement Trust Board,
Mysore.

Subject: Revised estimate for forming a layout of sites behind All India Radio, Yadavagiri, (First stage).

-:-

With reference to your letter No. D2.C.514/54-55 dated 27-1-1955, on the above subject, I am directed to state as follows:-

The estimate does not admit of any technical scrutiny for want of the particulars detailed below:-

a) Except for a layout plan, no detailed drawings are furnished in respect of the slabbed drains, box drains, road tunnels, pipe crossings, cisterns, retaining walls, construction of steps on the Northern side of the layout & etc. The quantities provided for in the estimate do not admit of any verification in the absence of detailed drawings.

b) The layout plan furnished does not indicate the proposed water supply and sewage lines. Three dotted lines are shown running right across the layout. In case they are power lines, it is imperative to avoid formation of sites below or very near the power lines. From the layout plan furnished, it is seen that the Power lines cross the sites numbered 4,7,41, and 46 and run very close to the sites numbered 8 and 29.

c) The estimate amounting to Rs. 3,275/- in respect of water supply stated to have been received from the Water Supply Division, has not been furnished.

d) Information as to when the work was started and completed and if the approved schedule rates of the year during which the several items of work were completed, are provided for in respect of the non-tendered items, is not furnished.

e) It is stated that the total area of the sites formed now (as per the revised estimate) is 11,463 s.yds., as against the area of 3,947 s.yds., originally proposed to be formed. These details as well as the roads actually formed are not indicated in the layout plan.

In the light of the above remarks, the records are returned herewith for retransmission with all the particulars

P.T.O.

(8)

required to facilitate scrutiny of the estimate.

Yours faithfully,

(V.Hanumanthappa)
Asst.Secretary to Government,
Education & L.S.G.Departments.

HGN.2/15-4.

No. D2.C.514/54-55.

Encl. One file.

OFFICE OF THE CHAIRMAN,
CITY IMPROVEMENT TRUST BOARD,
POST BOX NO. 55, MYSORE.

Dated..28th..June....*195* 5..

FROM

SRI S. LINGANNA,
Chairman, City Improvement Trust Board,
MYSORE.

To

.....Sri..B.M.Krishnan,..B.A.,I.A.S.,
Secretary to the Government of Mysore.
Education and *Local Self-Government* Departments,
BANGALORE.

SIR,

Subject : Revised estimate for forming a layout of sites behind All India Radio, Yadavagiri Extension. (First stage)

With reference to your letter No.L.870/I.T.B.17-55-4 dated 20-4-1955 returning the above estimate for want of the following particulars etc., I write to retransmit the estimate, furnishing the following points.

(a) Detailed layout plans showing the position of slabbed drains, box drains, road, tunnels, pipe crossings, cisterns, retaining walls, construction of steps etc. are herewith enclosed (Plan Nos. 1 and 2).

(b) The proposed water supply and underground drainage lines are noted in the enclosed plan No.3. The dotted lines shown on the plan are existing water mains. No buildings are put up in the position where these main run.

(c) Detailed estimate for Rs.3480/- in respect of water supply, received from the Water Supply Department is herewith enclosed.

(d) The work was started during the year 1953-54 and the same is under progress. The rates provided in the estimate are as per tender rates for tendered items and schedule of rates of 1953-54 for non-tendered items.

(e) The total area of the sites formed now against the original proposal, are shown in the enclosed plan (No.1

In the light of the above, I request you kindly to obtain and communicate the sanction of Government to the revised estimate at a very early date.

Necessary records accompany.

Yours faithfully,

S. Linganna 28/6/55

(S.Linganna)
Chairman.

DVS:

OFFICE NOTE:

(12)

Sub:- Revised estimate for the formation of a layout behind All India Radio, Yadavagiri Extension, Mysore.

The estimate is, subject to the following observations, scrutinized for Rs. 39,000/

The nature of the estimate is such that it is not susceptible of detailed scrutiny of all items of work as it provides for a number of improvements to the existing roads such as regrading roads, revetment, road crossings, farming portions of new roads and etc., Further, detailed drawings are not furnished in respect of the several road crossings, retaining walls &etc., provided for in the estimate. Hence, only such of the items of work as are amenable to scrutiny are checked, the quantities in respect of the other items of work being checked arithmetically. A)

It is seen that none of the roads proposed to be newly formed and those proposed to be improved are provided with rough stone pitching or curb stones on either side This is necessary especially in the case of the roads proposed to be asphalted to prevent creep of metal and asphalt at the sides. 3

It is not known why provision in respect of tools and plant and establishment charges is omitted. 4

The rates provided for are verified and corrected with reference to the copy of the tender rate list made available. Detailed cost data in respect of all non-tendered and non-scheduled items of work (indicated in the estimate) may be got up at the time of execution of the work. B) 5

From the plans furnished it is seen that the sites bearing numbers 26 to 35 do not get the benefit of water supply and sanitary services. 6

It is seen from the plan that the three existing water mains cross the sites numbered 41,7, 4 and 46. This has to be avoided. 7

With regard to water supply, two estimates are furnished, one in respect of lowering the 3" pipe line behind Akashvani Station and the other in respect of laying a 1½" G.I. pipe line. The provisions made in the estimates cannot be checked as the existing lines, the proposed ones, the extent to which the existing lines are proposed to be lowered or removed &etc., are not indicated in the plan. A 8

Provision is seen to have been made for removing 270 running feet of 3" C.I. pipe lines and laying only 10 plus Nos. or 162 R.ft. of 3" C.I. pipes. The released 3" pipes which are not made use of again should be valued and the cost credited to the estimated amount. 9

It is seen that the size of the new sub-mains proposed is 1½", but it is usual to provide for sub-mains of not less than 3" size. 10

IS.

R. Narayana Swamy 26/9

For CHIEF ENGINEER.

26-9-55

No. L 9905/STB.17-55-15
Dt 11-11-55 W/R.

To (11)

The chairman myore Town Board.

Sir,

Subject:- Revised estimate for forming a layout of roads behind All India Radio, Yadavagiri Extension (First stage)

With reference to your letter No Dy.C. 514/54-55 dated 28.6.55 on the above subject I am directed to observe as follows:-

The nature of the estimate is such that it is not susceptible of detailed scrutiny of all items of work as it provides for a number of improvements to the existing roads such as regrading roads, revetment, road crossings, forming portions of new roads and etc. Further, detailed drawings are not furnished in respect of the several road crossings, submissing walls etc. provided for in the estimate.

It is seen that none of the roads proposed to be newly formed and more proposed to be improved are provided with rough stone pitching or curb stone on either side. This is necessary especially in the case of the roads proposed to be asphalted to prevent creep of metal and asphalt at the sides.

P.T.O.

It is not known why provision in respect of lock and plants and establishment charges is omitted

Detailed cost data in respect of all non tendered and non Scheduled items of work (as indicated in the estimate) may be got up at the time of execution of the work

From the plan furnished it is seen that the sites bearing numbers 26 to 35 do not get the benefit of water supply and Sanitary service

It is seen from the plan that the three existing water mains cross the sites numbered 41, 7, 4 and 66. This has to be avoided

With regard to water supply two schemes are furnished, one in respect of lowering the 3" pipe line behind Akkarasi Station and the other in respect of laying 4½" G.I. pipe line The provision made in the estimates cannot be charged to the existing lines, the proposed ones, the extent to which the existing lines are proposed to be lowered or removed are not indicated in the plan.

Contd...

(13)

provision is seen to have been made for removing 270 running feet of 3" C. I pipe lines and laying only 10 plus 8 nos or 162 R.ft of 3" C.I pipes. The released 3" pipes which are not made use of again should be valued and the cost credited to the estimated amount

It is seen that the size of the new sub mains proposed is 1½" but it is usual to provide for sub mains of not less than 3" of size.

The records are herewith sent for redraundting the same with necessary modifications in the light of the observations made above

Yours affly

5/11

For Engr Exec & Dy Engrs

Dy 12/11/58 Mg

No.L.9905/9TO.17-55-15 W/R
D 11-11-55

(14)

The
Education & L.S.G.Departments

The Chairman,
City Improvement Trust Board,
Mysore.

Sir,

Subject: Revised estimate for forming a layout of sites behind All India Radio. Yadavagiri Extension (First stage)

- -

With reference to your letter No.D2.C.514/54-55 dated 28-6-1955 on the above subject, I am directed to observe as follows:-

The nature of the estimate is such that it is not susceptible of detailed scrutiny of all items of work as it provides for a number of improvements to the existing roads such as regrading roads, revetment, road crossings, forming portions of new roads and etc., Further detailed drawings are not furnished in respect of the several road crossings, retaining walls etc., provided for in the estimate.

It is seen that none of the roads proposed to be newly formed and those proposed to be improved are provided with rough stone pitching or curb stones on either side. This is necessary especially in the case of the roads proposed to be asphalted to prevent creap of metal and asphalt at the sides.

It is not known why provision in respect of tools and plant and establishment charges is omitted.

Detailed cost data in respect of all non-tendered and non-scheduled items of work (indicated in the estimate) may be got up at the time of execution of the work.

From the plan furnished it is seen that the sites bearing numbers 26 to 35 do not get the benefit of water supply and sanitary service.

It is seen from the plan that the three existing water mains

cross the sites numbered 41, 7, 4 and 46. This has to be avoided.

With regard to water supply two estimates are furnished, one in respect of lowering the 3" pipe line behind Akashavani Station and the other in respect of laying 1½" G.I.pipe line. The provision made in the estimates cannot be checked as the existing lines, the proposed ones the extent to which the existing lines are proposed to be lowered or removed etc., are not indicated in the plan.

Provision is seen to have been made for removing 270 running feet of 3" C.I.pipe lines and laying only 10 + 8 nos or 162 running feet of 3" C.I.pipes. The released 3" pipes which are not made use of again should be valued and the cost credited to the estimated amount.

It is seen that the ~~mix~~ size of the new sub-mains proposed is 1½" but it is usual to provide for sub-mains of not less than 3" of size

The records are herewith sent for retransmitting the same with necessary modification in the light of the observation made above.

Yours faithfully,

(V.Hanumanthappa)
for Secretary to Government,
Education & L.S.G.Departments.

knr-2/10/11

No. D2.C.514/54-55.
Encl. File of records.

6294
29 NOV 1955
MUNICIPAL BRANCH

(16)

OFFICE OF THE CHAIRMAN,
CITY IMPROVEMENT TRUST BOARD,
POST BOX NO. 55, MYSORE.

Dated November 23, 1955.

FROM

SRI S. LINGANNA,
Chairman, City Improvement Trust Board,
MYSORE.

To

9TP. 17-55-16

Sri B.H.Krishnan, B.A., I.A.S.,
Secretary to the Government of Mysore.
Education & Local Self-Government Departments.
BANGALORE.

SIR,

Subject : Revised estimate for forming a layout of sites behind All India Radio, Yadavagiri Extension. (First stage).

With reference to your letter No.L.9905/ITB.17-55-15 dated 11-11-55 returning the revised estima e for Rs.39,000/- for the above work, with certain observations, I write to retransmit the entire file of papers after attending to the same, and to state as follows:-

Re: the observations made in the first para of the letter, the estimate is got up as per actual execution. The present revised estimate is entirely in accordance with the work, as per actual execution and as the items are numerous, drawings cannot be furnished for all the minor items. Hence the provisions may be retained.

2. As the estimate for asphalting the roads and circle is based on the working rates of the City Municipal Council, vide remarks made in the estimate for Rs.7875/- at Rs.25/- per square, no separate provision is made for pitching and curbing. However, details will be worked out for Rs.7875/- providing for all the items of works required before taking up asphalting. Hence this provision may be retained.

3. As already intimated, in order to minimise the amount of the estimate, only the temporary establishment charges are provided for in the estimate. The usual establishment, tools and plant charges will be included along with other layout charges, such as underground drainage, water supply etc., and added on to the cost price of the houses to be built and disposed of.

4. Detailed cost data in respect of all non-tendered and non-scheduled items of work as indicated in the estimate will be got up at the time of execution of the work.

5. Water supply and underground drainage facilities to sites bearing Nos. 26 to 35 have been proposed in the second stage of the same layout, for which an estimate for Rs.21,000/- has been separately forwarded for sanction. Hence they are omitted in this estimate.

6. The water mains do not cross the sites as observed. The formation of sites has been so done that the sites do not interfere with the water mains. In the case of sites Nos. 41 and 46, the proposed buildings will be just away from the mains, though the latter pass through the sites.

P.T.O.

(17)

7. As regards water supply sub mains, the method of execution of water supply works, has already been reported to Government in the case of Adipampa Road layout. Based on the detailed estimate furnished by the Water Supply Department, these have been provided. Further details required in this behalf will have to be obtained from the Water Supply Department. Hence the provision may be retained.

In the above circumstances, I request early communication of sanction of Government to the Revised Estimate for Rs.39,000/-

Yours faithfully,

S. Linganna.
(S.Linganna)
Chairman.
23/11

DVS)

C. F. 74] **Routine Note.**

[To be used only for notes, requisitions, etc., not intended for permanent record.]

WD 0262—GPB—35,000—52 6-55

EDUCATION & L.S.G.S. 15

1327 · 17

No. D2.C.514/54-55.
Encl.

OFFICE OF THE CHAIRMAN,
CITY IMPROVEMENT TRUST BOARD,
POST BOX NO. 55, MYSORE.

Dated 12-5-1956.

FROM

SRI S. LINGANNA,
Chairman, City Improvement Trust Board,
MYSORE.

To

~~Sri~~ B.M.Krishnan, B.A., I.A.S.,
Secretary to the Government of Mysore.
Education & Local Self-Government Departments,
BANGALORE.

SIR,

Subject: Revised estimate for Rs.39,000/- for forming layout of sites behind All India Radio, Yadavagiri (First stage).

In inviting your kind reference to this office letter of even No. dated 3-1-1955 and subsequent correspondence on the above subject, I write to request you kindly to obtain and communicate the sanction of Government to the revised estimate early.

Yours faithfully,

S. Linganna 12/5

(S.Linganna)
Chairman.

DVS)

N.B.—Should routine notes be written on small slips the notes must be copied, or slips pasted on this form

M. G.S. App. F VI—G. 2]

18

SUBJECT.....

.....

.....

Diary No. of letter replied to.....

Section ITD

Serial No. 1755

File No. 19

Mysore Government Secretariat

( )

the *195*

Proceedings of the Government of Mysore

Date of issue.....195

Signed by.....

Read— G.O.No DL 2/30-31/ITB 1853-38 dated 9.1.54 according sanction to the Scheme for the Construction of 16 Model houses in the layout behind All India Radio Yadavagiri Extension Order thereon.—No. Mysore.

(2) Correspondence ending with this No. D2 C 514/54-55 dated 23rd nil 1955 from the Chairman MTB. forwarding a Revised estimate for Rs 39/000/- for the formation of a layout of sites behind All India Radio Yadavagiri Extension Mysore (First Stage) and sanctioning thereon an estimate for Rs 10,000

May this be—

(i) printed ?

(ii) treated as a Standing Order ?

(iii) published in the Gazette, English Part ?

(iv) translated ?

(v) placed at the disposal of the Press ?

(vi) published in the Gazette, Kannada Part ?

Page (16)

19

was launched by the Boss for
forming a layout of cats whiskers
on Indica Radio unit which was
intended for forming 16 nits only
to Cowbrick House here on and
most of the layout works were
completed after calling for tenders
and that during the course of
excavation of the layout works some
more area could be reclaimed
and more cats formed and clear
Accordingly a revised estimate for
Rs 39,000/- for forming additional
works involved has been got up
which includes provision for underground
drainage at a cost of Rs 7,000/- and
for water supply works at a cost of
Rs 3,275/- and engineering charges

List of Enclosures.

Copied by

Examined by

WD 03540—GPB—40,000—13-8-53

M. G. S. App. F. G. 31

MYSORE GOVERNMENT

SECRETARIAT.

(Continuation sheet draft form).

20

to the Revised estimate for Rs 39,000/-
and adding that the total site area
according to the revised layout
will be 81,463 Syds as against the
original proposal of for 16 nts of
3967 Syd; the average cost per Syd
being Rs 3-7-0.

~~Ordered~~

(3) Lr No ND 10623/A355-6 dated
25/5/56 from the Chief Engineer
duly forwarding the estimate with
certain observations

Ordered 4165-67
02-6-56

The Revised estimate for
Rs 39,000/- (Rupees thirty nine thousand
only) as scrutinised by the CE is
sanctioned. with the following observations

Include Para 6&7 of Page 10

page (10)

With regard to water supply two
estimates are forwarded one in
respect of lowering the 3" pipe line
behind Akasharam Station and the
other in respect of laying 1½" GI
pipe line The provision marked

WD 0258--GPB--PZS-1,20,000--1-7-55.

PROCEEDINGS OF THE GOVERNMENT OF MYSORE.

READ:-

Government Ofder No.L.13130-31/ITB. 18-53-38 dated 9-1-54 according sanction to the scheme for the construction of sixteen model houses in the layout behind All India Radio, Yadavagiri Extension, Mysore.

2. Correspondence ending with letter No.D2.C.514/54-55 dated 23-11-1954 from the Chairman, City Improvement Trust Board, Mysore, stating that an estimate for Rs.10,000/- was sanctioned by the Board for forming a layout of sites behind All India Radio, work of which was intended for forming sixteen sites only to construct model houses thereon and most of the layoutworks were completed after calling for tenders and that during the course of execution of the layout works some more area could be realigned and more sites formed and that accordingly a revised estimate for Rs.39,000/- for providing additional works involved has been got up which includes provision for underground drainage at acost of Rs.7,000/- and for water supply works at a cost of Rs.3,275/- and requesting sanction to the revised estimate for Rs.39,000 and adding that the total site area according to the revised layout will be 11,463 sq. yds as against the orginal proposal for sixteen sites of 3,947 sq. yds, the average cost per square yard being Rs.3-7-0.

3. Un-official Note No.10623/RB. 55-56 dated 25-1-1956 from the Chief Engineer of Mysore duly scrutinising the estimate with certain observations.

-:-

ORDER NO.L. 4165-67/9711-57-19

Dated, Bangalore, the 2-6-57

The revised estimate for Rs.39,000/- (Rupees thirtynine thousand only) as scrutinised by the Chief Engineer is sanctioned with the following observations:-

i) that from the plans furnished it is seen that sites bearing numbers 26 to 35 do not get the benefit of water supply and sanitary services;

ii) it is seen from the plan that the three existing water mains cross the sites numbered 41, 7, 4 and 46. This has to be avoided.

P.T.O

25

2. With regard to water supply two estimates are forwarded one in respect of lowering the 3" pipe line behind Akashavani Station and the other in respect of laying 1½" G.I.pipe line. The provision made in the estimates ~~xxxx~~ cannot be checked as the existing lines, the proposed ones, the extent to which the existing lines are proposed to be lowered or renewed etc., are not indicated in the plan.

3. Provision is seen to have been made for removing 270 R.Ft. of 3" G.I.Pipe lines and laying only 10 pieces 8 Nos or 162 R.Ft. of 3" C.I pipes. The release of 3" pipes which are not made use of again should be valued and the cost credited to the estimated amount.

4. It is seen that the size of the new sub-mains proposed is 1½" but it is usual to provide for sub-mains of not less than 3" size.

5. The points observed in respect of water supply are to be borne in mind while executing the work.

(V.Hanuma thappa)
for Secretary to Government,
Education & L.S.G.Departments.

To

The Chairman, City Improvement Trust Board, ~~xxxxxxxx~~ Mysore, with records

" Controller, State Accounts Department, Bangalore.

" Chief Engineer of Mysore, Bangalore.

knr-6/31.5

PROCEEDINGS OF THE GOVERNMENT OF MYSORE.

READ:-

Government Ofder No.L.13130-31/ITB. 18-53-38 dated 9-1-54 according sanction to the scheme for the construction of sixteen model houses in the layout behind All India Radio, Yadavagiri Extension, Mysore.

2. Correspondence ending with letter No.D2.C.514/54-55 dated 23-11-1954 from the Chairman, City Improvement Trust Board, Mysore, stating that an estimate for Rs.10,000/- was sanctioned by the Board for forming a layout of sites behind All India Radio, work of which was intended for forming sixteen sites only to construct model houses thereon and most of the layoutworks were completed after calling for tenders and that during the course of execution of the layout works some more area could be realigned and more sites formed and that accordingly a revised estimate for Rs.39,000/- for providing additional works involved has been got up which includes provision for underground drainage at acost of Rs.7,000/- and for water supply works at a cost of Rs.3.275/- and requesting sanction to the revised estimate for Rs.39,000 and adding that the total site area according to the revised layout will be 11,463 sq. yds as against the orginal proposal for sixteen sites of 3,947 sq. yds, the average cost per square yard being Rs.3-7-0.

3. Un-official Note No.10623/RB. 55-56 dated 25-1-1956 from the Chief Engineer of Mysore duly scrutinising the estimate with certain observations.

ORDER NO.L. 4165-67/57-58-19

Dated, Bangalore, the 2-6-58

The revised estimate for Rs.39,000/- (Rupees thirtynine thousand onl as scrutinised by the Chief Engineer is sanctioned with the following observations:-

i) that from the plans furnished it is seen that sites bearing numbers 26 to 35 do not get the benefit of water supply and sanitary services;

ii) it is seen from the plan that the three existing water mains xxxxx cross the sites numbered 41, 7, 4 and 46. This has to be avoided.

P.T.O